




K2 SingleRail mounting kit - landscape modules

3 module rows - 2 to 8 modules per row

Complete scope of delivery for each layout

Two mounting options are available: either the two blue items or the two green items are supplied. All neutral items are included with both options.

Layout	Option 1: roof hooks		Option 2: replacement metal tiles		Included with both options									
	Roof hooks	Timber screws 8 x 100 mm	Replacement metal tile incl. bracket	Rail connection kit	SingleRail 36 rails	Rail connectors	Cross connectors	End clamps	Mid clamps	End caps	BlackCover trim	Lightning protection clamps	Module grounding TerraGrif	Cable managers
3 x 2 6 modules 	22	50	22	22	8 x 3,65 m	-	20	20	20	16	16	10	6	6
3 x 3 9 modules 	35	100	35	35	6 x 3,65 m 4 x 5,95 m	-	30	20	20	20	32	10	9	9
3 x 4 12 modules 	43	100	43	43	4 x 2,40 m 8 x 3,65 m 4 x 4,80 m	10	40	20	20	24	32	10	12	12
3 x 5 15 modules 	56	150	56	56	10 x 3,65 m 8 x 4,80 m	10	40	20	20	28	32	10	15	15
3 x 6 18 modules 	65	150	65	65	12 x 3,65 m 4 x 4,80 m 4 x 5,95 m	10	50	40	40	32	32	10	18	18
3 x 7 21 modules 	77	200	77	77	18 x 3,65 m 8 x 4,80 m	10	60	40	40	36	48	10	21	21
3 x 8 24 modules 	85	200	85	85	4 x 2,40 m 16 x 3,65 m 8 x 5,95 m	10	70	40	40	40	48	10	24	24

Quantities include reserve allowance and packaging rounding. Rail lengths are supplied lengths.

 Roof hooks + screws





 Replacement metal tiles + connection kit

K2 SingleRail mounting kit - landscape modules

4 module rows - 2 to 8 modules per row

Complete scope of delivery for each layout

Two mounting options are available: either the two blue items or the two green items are supplied. All neutral items are included with both options.

Layout	Option 1: roof hooks		Option 2: replacement metal tiles		Included with both options									
	Roof hooks	Timber screws 8 x 100 mm	Replacement metal tile incl. bracket	Rail connection kit	SingleRail 36 rails	Rail connectors	Cross connectors	End clamps	Mid clamps	End caps	BlackCover trim	Lightning protection clamps	Module grounding TerraGrif	Cable managers
4 x 2 8 modules 	22	50	22	22	4 x 3,65 m 4 x 4,80 m	-	20	20	20	16	16	10	8	8
4 x 3 12 modules 	31	100	31	31	10 x 4,80 m	-	30	20	20	20	32	10	12	12
4 x 4 16 modules 	43	100	43	43	4 x 2,40 m 12 x 4,80 m	10	40	20	40	24	32	10	16	16
4 x 5 20 modules 	56	150	56	56	18 x 4,80 m	10	40	20	40	28	32	10	20	20
4 x 6 24 modules 	65	150	65	65	16 x 4,80 m 4 x 5,95 m	10	50	40	40	32	32	10	24	24
4 x 7 28 modules 	77	200	77	77	4 x 3,65 m 22 x 4,80 m	10	60	40	60	36	48	10	28	28
4 x 8 32 modules 	85	200	85	85	4 x 2,40 m 16 x 4,80 m 8 x 5,95 m	10	70	40	60	40	48	10	32	32

Quantities include reserve allowance and packaging rounding. Rail lengths are supplied lengths.



 Roof hooks + screws  Replacement metal tiles + connection kit

K2 SingleRail mounting kit - landscape modules

5 module rows - 2 to 8 modules per row

Complete scope of delivery for each layout

Two mounting options are available: either the two blue items or the two green items are supplied. All neutral items are included with both options.

Layout	Option 1: roof hooks		Option 2: replacement metal tiles		Included with both options									
	Roof hooks	Timber screws 8 x 100 mm	Replacement metal tile incl. bracket	Rail connection kit	SingleRail 36 rails	Rail connectors	Cross connectors	End clamps	Mid clamps	End caps	BlackCover trim	Lightning protection clamps	Module grounding TerraGrif	Cable managers
5 x 2 10 modules 	27	100	27	27	5 x 3,65 m 4 x 5,95 m	-	20	20	20	18	32	10	10	10
5 x 3 15 modules 	43	100	43	43	11 x 5,95 m	-	30	20	40	22	32	10	15	15
5 x 4 20 modules 	54	150	54	54	5 x 2,40 m 5 x 4,80 m 8 x 5,95 m	10	40	20	40	26	32	10	20	20
5 x 5 25 modules 	70	150	70	70	10 x 4,80 m 10 x 5,95 m	10	50	20	40	30	32	10	25	25
5 x 6 30 modules 	80	200	80	80	5 x 4,80 m 17 x 5,95 m	10	60	40	60	34	48	10	30	30
5 x 7 35 modules 	95	200	95	95	5 x 3,65 m 10 x 4,80 m 14 x 5,95 m	10	70	40	60	38	48	10	35	35
5 x 8 40 modules 	105	250	105	105	5 x 2,40 m 26 x 5,95 m	10	80	40	80	42	48	10	40	40

Quantities include reserve allowance and packaging rounding. Rail lengths are supplied lengths.

 Roof hooks + screws

 Replacement metal tiles + connection kit