




K2 SingleRail mounting kit - portrait modules

2 module rows - 4 to 13 modules per row

Complete scope of delivery for each layout

Two mounting options are available: either the two blue items or the two green items are supplied. All neutral items are included with both options.

Layout	Option 1: roof hooks		Option 2: replacement metal tiles		Included with both options								
	Roof hooks	Timber screws 8 x 100 mm	Replacement metal tile incl. bracket	Rail connection kit	SingleRail 36 rails	Rail connectors	End clamps	Mid clamps	End caps	BlackCover trim	Lightning protection clamps	Module grounding TerraGrif	Cable managers
2 x 4 8 modules 	20	50	20	20	4 x 4,80 m	-	20	20	8	16	10	8	8
2 x 5 10 modules 	24	50	24	24	4 x 5,95 m	-	20	20	8	16	10	10	10
2 x 6 12 modules 	31	100	31	31	4 x 2,40 m 4 x 4,80 m	10	20	20	8	16	10	12	12
2 x 7 14 modules 	31	100	31	31	4 x 3,65 m 4 x 4,80 m	10	20	40	8	16	10	14	14
2 x 8 16 modules 	35	100	35	35	8 x 4,80 m	10	20	40	8	16	10	16	16
2 x 9 18 modules 	39	100	39	39	4 x 4,80 m 4 x 5,95 m	10	20	40	8	16	10	18	18
2 x 10 20 modules 	43	100	43	43	8 x 5,95 m	10	20	40	8	16	10	20	20
2 x 11 22 modules 	48	100	48	48	4 x 3,65 m 8 x 4,80 m	10	20	40	8	16	10	22	22
2 x 12 24 modules 	52	150	52	52	4 x 2,40 m 8 x 5,95 m	10	20	60	8	16	10	24	24
2 x 13 26 modules 	52	150	52	52	4 x 3,65 m 8 x 5,95 m	10	20	60	8	16	10	26	26

Quantities include reserve allowance and packaging rounding. Rail lengths are supplied lengths.

 Roof hooks + screws









 Replacement metal tiles + connection kit

K2 SingleRail mounting kit - portrait modules

3 module rows - 4 to 13 modules per row

Complete scope of delivery for each layout

Two mounting options are available: either the two blue items or the two green items are supplied. All neutral items are included with both options.

Layout	Option 1: roof hooks		Option 2: replacement metal tiles		Included with both options								
	Roof hooks	Timber screws 8 x 100 mm	Replacement metal tile incl. bracket	Rail connection kit	SingleRail 36 rails	Rail connectors	End clamps	Mid clamps	End caps	BlackCover trim	Lightning protection clamps	Module grounding TerraGrif	Cable managers
3 x 4 12 modules 	33	100	33	33	6 x 5,95 m	-	20	20	12	16	10	12	12
3 x 5 15 modules 	39	100	39	39	6 x 5,95 m	-	20	40	12	16	10	15	15
3 x 6 18 modules 	42	100	42	42	6 x 2,40 m 6 x 4,80 m	10	20	40	12	16	10	18	18
3 x 7 21 modules 	46	100	46	46	6 x 3,65 m 6 x 4,80 m	10	20	40	12	16	10	21	21
3 x 8 24 modules 	52	150	52	52	12 x 4,80 m	10	20	60	12	16	10	24	24
3 x 9 27 modules 	58	150	58	58	6 x 4,80 m 6 x 5,95 m	10	20	60	12	16	10	27	27
3 x 10 30 modules 	65	150	65	65	12 x 5,95 m	10	20	60	12	16	10	30	30
3 x 11 33 modules 	71	150	71	71	6 x 3,65 m 12 x 4,80 m	20	20	60	12	16	10	33	33
3 x 12 36 modules 	73	150	73	73	6 x 2,40 m 12 x 5,95 m	20	20	80	12	16	10	36	36
3 x 13 39 modules 	83	200	83	83	6 x 3,65 m 12 x 5,95 m	20	20	80	12	16	10	39	39

Quantities include reserve allowance and packaging rounding. Rail lengths are supplied lengths.

 Roof hooks + screws







 Replacement metal tiles + connection kit

K2 SingleRail mounting kit - portrait modules

4 module rows - 4 to 10 modules per row

Complete scope of delivery for each layout

Two mounting options are available: either the two blue items or the two green items are supplied. All neutral items are included with both options.

Layout	Option 1: roof hooks		Option 2: replacement metal tiles		Included with both options								
	Roof hooks	Timber screws 8 x 100 mm	Replacement metal tile incl. bracket	Rail connection kit	SingleRail 36 rails	Rail connectors	End clamps	Mid clamps	End caps	BlackCover trim	Lightning protection clamps	Module grounding TerraGrif	Cable managers
4 x 4 16 modules 	43	100	43	43	8 x 4,80 m	-	20	40	16	16	10	16	16
4 x 5 20 modules 	52	150	52	52	8 x 5,95 m	-	20	40	16	16	10	20	20
4 x 6 24 modules 	61	150	61	61	8 x 2,40 m 8 x 4,80 m	10	20	40	16	16	10	24	24
4 x 7 28 modules 	61	150	61	61	8 x 3,65 m 8 x 4,80 m	10	20	60	16	16	10	28	28
4 x 8 32 modules 	69	150	69	69	16 x 4,80 m	10	20	60	16	16	10	32	32
4 x 9 36 modules 	77	200	77	77	8 x 4,80 m 8 x 5,95 m	10	20	80	16	16	10	36	36
4 x 10 40 modules 	85	200	85	85	16 x 5,95 m	10	20	80	16	16	10	40	40

Quantities include reserve allowance and packaging rounding. Rail lengths are supplied lengths.

 Roof hooks + screws

 Replacement metal tiles + connection kit